

floorsNwalls

QUOTE

PROVIDER

floorsNwalls

Phone: _____

Email: _____

CUSTOMER INFO

Date: January 15, 2026

Customer: _____

Address: _____

PROJECT: BOILER PIPE ABATEMENT (8 TOTAL MAN-HOURS)

ITEM / MATERIAL DESCRIPTION	PRICE REFERENCE	TOTAL
Labor: 2-Person Certified Crew (4 hrs each)	Industry Avg: \$150/hr	\$1,200.00
6-Mil Poly Sheeting: 20' x 100' Roll (Containment)	View Price at Home Depot	\$110.00
Asbestos Bags: 6-Mil Printed Waste Bags (Roll)	View Price at Aramsco	\$85.00
Lockdown Encapsulant: Fiberset PM (5 Gal)	View Price at Aramsco	\$135.00
PPE: Tyvek Suits & P100 Filter Sets	View Price at Home Depot	\$65.00
Disposal Fees: Haz-Waste Facility Tipping Fees	Local Market Rate	\$325.00
Air Testing: Independent PCM Air Clearance	Third-Party Avg	\$650.00

Project Subtotal: \$2,570.00

ESTIMATED TOTAL: \$2,570.00

Authorized floorsNwalls Signature

Customer Signature

Labor reflects 2 technicians for 4 hours of on-site time. Prices are for materials only and do not include equipment rental (HEPA Scrubbers). All work strictly adheres to OSHA 29 CFR 1926.1101 standards.